



## Demolition of Waid Academy, Anstruther



**Location:**  
Waid Academy, Anstruther

**Client:**  
BAM

**Contract Start:**  
June 2017

**Programme:**  
12 Weeks

**Contract Value:**

**Services Provided:**

- Soft strip of structure in tandem whilst Licenced Asbestos Removal is being carried out to the AIB
- Removal of other Non-Licenced Asbestos to the various Outbuildings – AC Roof Sheets, Cold Store, Wall Panels, etc – by Daltons
- Hand Demolition and Mechanical Demolition
- Demolition of Structure including grubbing up slab & foundations.
- Removal of all other waste streams off site.

### Project Summary

Daltons Demolitions were appointed by BAM to carry out the demolition of the Former school Waid Academy in Anstruther, Fife. The works commenced on 19<sup>th</sup> June 2017 and lasted 12 weeks.

The works were broken down into five separate stages which helped the programme run smoothly and set targets which were strictly adhered to so the completion date was met.

Stage one was the soft strip works where the current building was taken back to the shell, asbestos was present so Phase 2 was the Asbestos Removal works Licenced Asbestos Removal works were carried out by our appointed Sub Contractor and the Non- Licenced Removal works were carried out by ourselves.

Stage 3 was the careful and intricate hand demolition works that were carried out to avoid the section of building which were still to remain to not be damaged. Stage 4 was the machine demolition which consisted of both 20/40 tonne Excavators with a selector grab controlled by a Banksman and a 2 way radio system.

After Stage 5 which was removal of floor slabs, foundations and general site clearance works all materials were segregated into the various waste streams and transported off site for recycling.

The project was completed with no incidents, on time within the scheduled programme and within the project cost budget.